BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/OW/WORK_INDENT24214

APPROVED SCHEDULE - B

.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

roviding and installation of water supply pipelines to existing water supply network in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hosahalli Jaganath Sanjay Reddy	
				In Figures	In Words
1	175.97	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	185.0	Rupees One Hundred Eighty Five Only
2	3200	Supplying PVC ring tight pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite rolling and lowering into trenches laying true line and level and perfect linking at joints testing and commissioning including loading and unloading at both destination and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approval type with all labour with all lead and lift including encasing the pipe alround to a depth of not less than 15 cms with soft gravel or selected earth available from the excavation etc., compelte and giving necessary hydraluic test to the required pressure as per IS (Contractor will make his own arrangement for procuring water for testing	Rmtr	70.0	Rupees Seventy Only
3	175.97	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item.	Cum	70.0	Rupees Seventy Only
4	78.21	Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the water at OMC in machanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	1700.0	Rupees One Thousand Seven Hundred Only
5	11.73	Providing, laying bituminous Concrete using 100/120 THP capacity H.M.P with Sensor paver Gr-II(30mm to 45mm), crushed aggregates of specified grading premixed with 6% CRMB 55 grade bituminous binder and , transporting the hot mix to work site , laying to the required level and grade, rolling with wheeled , vibratory and tandeem rollers to achieve the desired density including all leads and lift cost of all materials, labour, HOM of machineries complete as per specifications	Cum	9860.0	Rupees Nine Thousand Eight Hundred Sixty Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

08/03